MI TILE INSTALLATION EXPERTS

Floor tile planning checklist

Keep it with your project. Share it with your contractor.

- [ ] Identify concrete or wood structure; photograph the exposed base after demolition.
- [ ] Remove unsuitable adhesive, loose material and protruding staples / fasteners; verify a clean, sound base.
- [ ] For wood, assess stiffness, panel condition and fastening before selecting the approved underlayment.
- [ ] For concrete, assess cracks, moisture and contaminants before choosing the preparation system.
- [ ] Measure flatness separately from level; agree repairs, heights, doors and transitions.
- [ ] Confirm primer, leveling product, membrane and mortar compatibility as one assembly.
- [ ] Review tile dimensions, shade, caliber, batch quantity, bowing and the proposed layout.
- [ ] Plan movement joints, mortar coverage and the grout sample before setting tile.
- [ ] Decide tile baseboards, edge profiles, heating, toilets and other fixture resets.
- [ ] Agree furniture removal, access, cure time, material supply and change approvals.

Project notes